

土工数量計算書

測点	单距離	掘削			床掘			埋戻			路床盛土		
		断面積	平均	立積	断面積	平均	立積	断面積	平均	立積	断面積	平均	立積
B.P		0.10			2.40			1.10					
+8.0①	8.00	0.10	0.100	0.80	1.80	2.100	16.80	1.20	1.150	9.20			
+8.0②					1.90			1.20					
+14.3①	6.30				1.70	1.800	11.34	1.20	1.200	7.56			
+14.3②					1.70			1.40					
+20.8①	6.50	0.10	0.050	0.33	2.10	1.900	12.35	1.10	1.250	8.13			
+20.8②		0.10			2.00			1.20					
+28.4①	7.60		0.050	0.38	7.30	4.650	35.34	3.90	2.550	19.38			
+28.4②					7.30			3.90					
計	28.40			1.51			75.83			44.27			
		残土処理	77.34	-	44.27	/	0.90	=	28.15				

土工数量計算書

[illegible]

土留コンクリート擁壁工数量計算書

表法 1 :

裏法 1 : 0.50

天端幅= 0.50

砕石厚= 0.20

測 点	単距離	擁壁高	コンクリート					型 枠			基礎砕石		
			上幅	下幅	断面積	平均	立積	断面長	平均	面積	基整幅	平均	平米
B.P		1.00	0.50	1.00	0.750			2.118			1.10		
+8.0①	8.00	1.00	0.50	1.00	0.750	0.750	6.00	2.118	2.118	16.94	1.10	1.100	8.80
+8.0②		1.00	0.50	1.00	0.750			2.118			1.10		
+14.3①	6.30	1.00	0.50	1.00	0.750	0.750	4.73	2.118	2.118	13.34	1.10	1.100	6.93
+14.3②		1.00	0.50	1.00	0.750			2.118			1.10		
+20.8①	6.50	1.00	0.50	1.00	0.750	0.750	4.88	2.118	2.118	13.77	1.10	1.100	7.15
+20.8②		2.00	0.50	1.50	2.000			4.236			1.60		
+28.4①	7.60	2.00	0.50	1.50	2.000	2.000	15.20	4.236	4.236	32.19	1.60	1.600	12.16
+28.4②		2.00	0.50	1.50	2.000			4.236			1.60		
計	28.40						30.81			76.24			35.04

水路擁壁工数量計算書

表法 1 : 0.30

裏法 1 :

天端幅= 0.20

碎石厚=

測点	単距離	擁壁高	コンクリート					型枠			基礎碎石		
			上幅	下幅	断面積	平均	立積	断面長	平均	面積	基整幅	平均	平米
+14.3②		0.50	0.20	0.35	0.138			1.022			0.45		
+20.8①	6.50	0.50	0.20	0.35	0.138	0.138	0.90	1.022	1.022	6.64	0.45	0.450	2.93
計	6.50						0.90			6.64			2.93

舖裝面積計算書

表層 再生密粒度アスファルト t =40mm				上層路盤 粒調碎石 M=40 t =110mm				不陸整正及び下層路盤 RC-40-0 t =180mm			
測点	単距離	幅員	面積	測点	単距離	幅員	面積	測点	単距離	幅員	面積
B.P		4.00		B.P		1.50		B.P		1.40	
+8.0①	8.00	4.10	32.40	+8.0①	8.00	1.50	12.00	+8.0①	8.00	1.40	11.20
+8.0②		4.10		+8.0②		1.60		+8.0②		1.50	
+14.3①	6.30	4.00	25.52	+14.3①	6.30	1.50	9.77	+14.3①	6.30	1.40	9.14
+14.3②		4.00		+14.3②		1.50		+14.3②		1.40	
+20.8①	6.50	3.80	25.35	+20.8①	6.50	1.60	10.08	+20.8①	6.50	1.50	9.43
+20.8②		4.00		+20.8②		1.60		+20.8②		1.50	
+28.4①	7.60	3.90	30.02	+28.4①	7.60	2.70	16.34	+28.4①	7.60	2.60	15.58
+28.4②		3.90		+28.4②		2.70		+28.4②		2.60	
計	28.40		113.29	計	28.40		48.19	計	28.40		45.35