

土工数量計算書

測 点	単距離	掘 削			床 掘			埋 戻			路 床 盛 土		
		断面積	平均	立積	断面積	平均	立積	断面積	平均	立積	断面積	平均	立積
右側													
MC. 2-2. 274		0. 10											
MC. 2	2. 27	0. 10	0. 100	0. 23									
EC. 2	6. 32	0. 20	0. 150	0. 95									
BC. 3	9. 41	0. 20	0. 200	1. 88									
MC. 3	5. 01	0. 20	0. 200	1. 00									
No. 3	2. 14	0. 20	0. 200	0. 43									
EC. 3	2. 87	0. 20	0. 200	0. 57									
BC. 4	5. 13	0. 20	0. 200	1. 03									
MC. 4	20. 01	0. 20	0. 200	4. 00									
左側													
EC. 4					3. 20			2. 60					
BC. 5	7. 40				4. 20	3. 700	27. 38	2. 40	2. 500	18. 50			
No. 5	3. 98				4. 20	4. 200	16. 72	2. 40	2. 400	9. 55			
MC. 5①	8. 59				3. 60	3. 900	33. 49	2. 10	2. 250	19. 32			
MC. 5②					7. 40			2. 10					
EC. 5	12. 57				1. 80	4. 600	57. 81	0. 50	1. 300	16. 34			
No. 6	9. 33				3. 60	2. 700	25. 20	2. 30	1. 400	13. 07			
No. 7	30. 00	1. 00	0. 500	15. 00	2. 30	2. 950	88. 50	1. 20	1. 750	52. 50			
水路箇所													
A-A							1. 60	0. 80			0. 40		
B-B	7. 00							0. 40	0. 600	4. 20	0. 20	0. 300	2. 10
C-C	7. 50				0. 10	0. 050	0. 38		0. 200	1. 50	1. 20	0. 700	5. 25
D-D	6. 00						1. 24	0. 30	0. 150	0. 90	1. 60	1. 400	8. 40
計	145. 54			25. 09			252. 32			135. 88			15. 75
残土処理		277. 41	-	151. 63	/	0. 90	=	108. 93					

土工数量計算書

測 点	単距離	舗装版切断		構造物取壊し			間詰コンクリート			As舗装版取壊しt=4cm		
		t =4cm	距離	断面積	幅	立積	断面積	幅	立積	距離	幅	面積
右側												
MC. 2-2. 274												
MC. 2	2. 27											
EC. 2	6. 32											
BC. 3	9. 41											
MC. 3	5. 01											
No. 3	2. 14											
EC. 3	2. 87											
BC. 4	5. 13											
MC. 4	20. 01											
左側												
EC. 4			0. 50	0. 60						0. 40		
BC. 5	7. 40		7. 40	0. 40	0. 500	3. 70					0. 200	1. 48
No. 5	3. 98		3. 98	0. 40	0. 400	1. 59						
MC. 5①	8. 59		8. 59	0. 40	0. 400	3. 44						
MC. 5②				0. 70								
EC. 5	12. 57		12. 57	0. 30	0. 500	6. 28						
No. 6	9. 33		9. 33	0. 30	0. 300	2. 80						
No. 7	30. 00		31. 00		0. 150	4. 50						
水路箇所												
A-A							0. 20			2. 20		
B-B	7. 00						0. 20	0. 200	1. 40	3. 40	2. 800	19. 60
C-C	7. 50						0. 20	0. 200	1. 50		1. 700	12. 75
D-D	6. 00						0. 20	0. 200	1. 20	2. 00	1. 000	6. 00
計	145. 54		73. 37			22. 31			4. 10			39. 83
		汚泥体積 (m3)		0. 07						殻体積 (m3)		1. 59

土留コンクリート擁壁工数量計算書

裏法 1 :

碎石厚= 0.20

測点	単距離	擁壁高	コンクリート					型枠			基礎碎石		
			上幅	下幅	断面積	平均	立積	断面長	平均	面積	基整幅	平均	平米
左側													
EC. 4		1.80	0.20	0.74	0.846			3.679			0.84		
BC. 5	7.40	1.30	0.20	0.85	0.683	0.765	5.66	2.657	3.168	23.44	0.95	0.895	6.62
No. 5	3.98	1.55	0.20	0.98	0.915	0.799	3.18	3.168	2.913	11.59	1.08	1.015	4.04
MC. 5①	8.59	1.20	0.20	0.56	0.456	0.686	5.89	2.453	2.811	24.14	0.66	0.870	7.47
MC. 5②		2.20	0.20	0.86	1.166			4.497			0.96		
EC. 5	12.57	0.60	0.20	0.38	0.174	0.670	8.42	1.226	2.862	35.97	0.48	0.720	9.05
No. 6	9.33	1.35	0.20	0.61	0.547	0.361	3.37	2.759	1.993	18.60	0.71	0.595	5.55
No. 7	30.00	0.90	0.20	0.47	0.302	0.425	12.75	1.840	2.300	69.00	0.57	0.640	19.20
計	71.87						39.27			182.74			51.93

路側ブロック積工数量計算書

裏込除高 = 0.30

表法 1 : 0.40

裏コンクリート厚 = 0.10

[illegible]

小口止工数量計算書

碎石厚= 0.20

測点	単距離	擁壁高	コンクリート					型枠			基礎碎石		
			上幅	下幅	断面積	平均	立積	断面長	平均	面積	基整幅	平均	平米
BC. 5+2. 12													
BC. 5+2. 42	0. 30	1. 73					0. 35			2. 33			0. 20
計	0. 30						0. 35			2. 33			0. 20

ガードレール基礎工数量計算書

表法 1 : 0.50

裏法 1 :

天端幅= 0.50

砕石厚=

測 点	単距離	擁壁高	コンクリート					型 枠			基礎砕石		
			上幅	下幅	断面積	平均	立積	断面長	平均	面積	基整幅	平均	平米
No. 4		0.70	0.50	0.85	0.473			1.483					
EC. 4	20.01	0.70	0.50	0.85	0.473	0.473	9.47	1.483	1.483	29.68			
BC. 5	7.40	0.70	0.50	0.85	0.473	0.473	3.50	1.483	1.483	10.97			
BC. 5+2. 12	2.12	0.70	0.50	0.85	0.473	0.473	1.00	1.483	1.483	3.14			
計	29.53						13.97			43.79			

現場打水路擁壁工数量計算書

表法 1 : 0.20

裏法 1 :

天端幅= 0.20

碎石厚= 0.10

測点	単距離	擁壁高	コンクリート					型枠			基礎碎石		
			上幅	下幅	断面積	平均	立積	断面長	平均	面積	基整幅	平均	平米
No. 3+13.2		0.50	0.20	0.30	0.125			1.010			0.40		
MC. 4-3.0	3.54	0.50	0.20	0.30	0.125	0.125	0.44	1.010	1.010	3.58	0.40	0.400	1.42
計	3.54						0.44			3.58			1.42

舖裝面積計算書

表層 再生密粒度アスファルト t =40mm				上層路盤 RC-40-0 t =150mm				不陸整正及び下層路盤 RC-40-0 t =180mm			
測点	単距離	幅員	面積	測点	単距離	幅員	面積	測点	単距離	幅員	面積
右側				右側				右側			
MC. 4-6. 54	6. 54			MC. 4-6. 54	6. 54	1. 60	5. 23	MC. 4-6. 54	6. 54	1. 60	5. 23
No. 4	1. 12			No. 4	1. 12	1. 60	1. 79	No. 4	1. 12	1. 60	1. 79
EC. 4	20. 01			EC. 4	20. 01	0. 80	24. 02	EC. 4	20. 01	0. 80	24. 02
BC. 5	7. 40			BC. 5	7. 40	1. 70	9. 25	BC. 5	7. 40	1. 70	9. 25
No. 5	3. 98			No. 5	3. 98	0. 60	4. 58	No. 5	3. 98	0. 60	4. 58
左側				左側				左側			
EC. 4				EC. 4		0. 80		EC. 4		0. 80	
BC. 5	7. 40			BC. 5	7. 40	1. 70	9. 25	BC. 5	7. 40	1. 70	9. 25
No. 5	3. 98			No. 5	3. 98	2. 10	7. 56	No. 5	3. 98	2. 10	7. 56
MC. 5①	8. 59			MC. 5①	8. 59	1. 90	17. 18	MC. 5①	8. 59	1. 90	17. 18
MC. 5②				MC. 5②		2. 00		MC. 5②		2. 00	
EC. 5	12. 57			EC. 5	12. 57	2. 00	25. 14	EC. 5	12. 57	2. 00	25. 14
No. 6	9. 33			No. 6	9. 33	2. 00	18. 67	No. 6	9. 33	2. 00	18. 67
No. 7	30. 00			No. 7	30. 00	4. 10	91. 50	No. 7	30. 00	4. 10	91. 50
計	110. 92			計	110. 92		214. 17	計	110. 92		214. 17

側溝及び集水桝計算書

自由勾配側溝			横断用自由勾配側溝			集水桝		
測 点	規格	距離	測 点	規格	距離	測 点	規格	数
右側			MC. 4-4. 86	300×700	3. 90	左側		
No. 4	300×500	1. 50	EC. 4-3. 88	300×600	3. 68	MC. 4-4. 86	300×300×1000	1. 00
	300×600	6. 00				EC. 4-3. 88	300×300×800	1. 00
+3. 704～								
EC. 4-3. 88	300×700	6. 00						
						右側		
						MC. 4-4. 86	300×300×1000	1. 00
						No. 4	500×500×1000	1. 00
						EC. 4-3. 88	500×500×800	1. 00
Co蓋	300用	10. 80						
グレイチング	300用 細目	2. 70						
						現場打集水桝	1000×1000×1000	1. 00
計		13. 50	計		7. 58	計		6. 00

鋪裝止擁壁工数量計算書

表法 1 :

裏法 1 :

天端幅= 0.20

碎石厚= 0.20

測点	単距離	擁壁高	コンクリート					型枠			基礎碎石		
			上幅	下幅	断面積	平均	立積	断面長	平均	面積	基整幅	平均	平米
BC. 5+2. 42		0. 40	0. 20	0. 20	0. 080			0. 800			0. 30		
No. 5	1. 56	0. 40	0. 20	0. 20	0. 080	0. 080	0. 12	0. 800	0. 800	1. 25	0. 30	0. 300	0. 47
計	1. 56						0. 12			1. 25			0. 47