

土工数量計算書

測 点	単距離	掘 削			床 掘			埋 戻		
		断面積	平均	立積	断面積	平均	立積	断面積	平均	立積
+29.0					0.5			0.3		
No. 4	1.0				0.5	0.49	0.5	0.3	0.26	0.3
+8.0	8.0				1.1	0.78	6.2	0.5	0.38	3.0
No. 5	22.0				0.5	0.80	17.6	0.3	0.41	8.9
+13.5	13.5				0.5	0.52	7.0	0.3	0.30	4.1
+17.9	4.4				0.5	0.52	2.3	0.3	0.30	1.3
No. 6	12.1				0.5	0.52	6.3	0.3	0.30	3.6
+7.0	7.0				0.6	0.54	3.8	0.3	0.31	2.1
小計	68.0				小計		43.6	小計		23.4
+10.4					0.5			0.3		
+19.4①	9.00				0.4	0.45	4.0	0.3	0.25	2.3
+19.4②					0.4			0.3		
+24.9①	5.50				0.4	0.41	2.3	0.3	0.30	1.7
+24.9②					0.4			0.3		
No. 1	5.10				0.6	0.50	2.5	0.3	0.30	1.5
+3.0①	3.00				0.6	0.55	1.7	0.3	0.30	0.9
+3.0②					0.7			0.3		
+12.0①	9.00				0.6	0.64	5.7	0.3	0.30	2.7
+12.0②					0.6			0.3		
+17.5	5.50				0.6	0.60	3.3	0.3	0.30	1.7
小計	37.1				小計		19.4	小計		10.7
合計	105.10	合計			合計		63.1	合計		34.0
		残土処理	63.1	-	34.0	/	0.9	=	25.2	m³

土工数量計算書

測 点	単距離	Co取壊し（無筋）			Co取壊し（有筋）			間詰Co			As取壊し			可変勾配側溝			
		断面積	平均	立積	断面積	平均	立積	断面積	平均	立積	幅員	平均	面積	起点	終点	種類	距離
+29.0		0.3						0.1			2.7			No. 3+29.0	No. 4+7.0	500×500	8.0
No. 4	1.0	0.3	0.33	0.33				0.1	0.07	0.1	2.7	2.70	2.70	No. 4+8.0	No. 4+28.0	500×500	20.0
+8.0	8.0	0.3	0.31	2.48				0.1	0.07	0.5	2.7	2.70	21.60	No. 4+28.0	No. 6+7.0	500×600	39.0
No. 5	22.0	0.4	0.36	7.81				0.1	0.07	1.5	2.0	2.35	51.70				
+13.5	13.5	0.4	0.40	5.40				0.1	0.08	1.1	2.0	2.00	27.00	As型可変側溝用柵			
+17.9	4.4	0.4	0.38	1.65				0.1	0.08	0.4	2.0	2.00	8.80	No. 4+7.0	No. 4+8.0	500×600	0.72m
No. 6	12.1	0.4	0.38	4.60				0.1	0.08	1.0	2.0	2.00	24.20				
+7.0	7.0	0.4	0.40	2.80				0.1	0.08	0.6	2.0	2.00	14.00	No. 4+8.0付近 横断水路		300×500	1.0m
小計	68.0	小計		25.07				小計		5.1	小計		150.00				
+10.4		0.3						0.1			3.5			+10.4	+18.4	500×500	8.0
+19.4①	9.00	0.3	0.28	2.52				0.1	0.12	1.0	3.6	3.55	31.95	+18.4	No. 1+17.5	500×600	29.0
+19.4②		0.3			0.1			0.1			3.6						
+24.9①	5.50	0.3	0.30	1.65	0.1	0.07	0.39	0.2	0.16	0.9	3.5	3.55	19.53				
+24.9②		0.3						0.2			3.5						
No. 1	5.10	0.3	0.30	1.50				0.2	0.18	0.9	3.5	3.50	17.85				
+3.0①	3.00	0.3	0.28	0.84				0.1	0.15	0.5	3.5	3.50	10.50				
+3.0②		0.2						0.1			3.7						
+12.0①	9.00	0.2	0.19	1.67				0.1	0.08	0.7	3.9	3.80	34.20				
+12.0②		0.2			0.1			0.1			3.9						
+17.5	5.50	0.2	0.21	1.16	0.1	0.09	0.47	0.1	0.08	0.4	4.0	3.95	21.73				
小計	37.1	小計		9.34	小計		0.86	小計		4.4	小計		135.76				
計	105.10	合計		34.4	合計		0.9	合計		9.5			285.8				104.0
		As舗装版切断	4.7	+	68.0	+	37.1*2	+	7.50	=	154.2	m		Co蓋(0.5m)	104 / (3/4)	78 枚	
		As濁水	0.023	×	0.04	×	154.20			=	0.14	m³		グレーチング(0.5m)	104/ 4	26 枚	

土工数量計算書

測 点	単距離	表層(再生密粒度(13)As t=4cm)			上層路盤工(M-40 t=11cm)			下層路盤工(RC-40 t=18cm)			不 陸 整 正		
		幅員	平均	面積	幅員	平均	面積	幅員	平均	面積	幅員	平均	立積
+29.0		2.7			0.5			0.5			2.2		
No. 4	1.0	2.7	2.70	2.7	0.5	0.50	0.5	0.5	0.500	0.50	2.2	2.20	2.2
+8.0	8.0	2.7	2.70	21.6	1.0	0.75	6.0	1.0	0.750	6.00	1.7	1.95	15.6
No. 5	22.0	2.0	2.35	51.7	0.5	0.75	16.5	0.5	0.750	16.50	1.5	1.60	35.2
+13.5	13.5	2.0	2.00	27.0	0.5	0.50	6.8	0.5	0.500	6.75	1.5	1.50	20.3
+17.9	4.4	2.0	2.00	8.8	0.5	0.50	2.2	0.5	0.500	2.20	1.5	1.50	6.6
No. 6	12.1	2.0	2.00	24.2	0.5	0.50	6.1	0.5	0.500	6.05	1.5	1.50	18.2
+7.0	7.0	2.0	2.00	14.0	0.5	0.50	3.5	0.5	0.500	3.50	1.5	1.50	10.5
小計	68.0	小計		150.0	小計		41.5	小計		41.50	小計		108.5
+10.4		3.6			0.5			0.5			3.1		
+19.4①	9.00	3.8	3.68	33.1	0.5	0.50	4.5	0.5	0.50	4.5	3.3	3.18	28.6
+19.4②		3.8			0.5			0.5			3.3		
+24.9①	5.50	3.7	3.73	20.5	0.5	0.50	2.8	0.5	0.50	2.8	3.2	3.23	17.7
+24.9②		3.7			0.5			0.5			3.2		
No. 1	5.10	3.6	3.63	18.5	0.5	0.50	2.6	0.5	0.50	2.6	3.1	3.13	15.9
+3.0①	3.00	3.6	3.58	10.7	0.5	0.50	1.5	0.5	0.50	1.5	3.1	3.08	9.2
+3.0②		3.8			0.5			0.5			3.3		
+12.0①	9.00	4.0	3.85	34.7	0.5	0.50	4.5	0.5	0.50	4.5	3.5	3.35	30.2
+12.0②		4.0			0.5			0.5			3.5		
+17.5	5.50	4.0	3.98	21.9	0.5	0.50	2.8	0.5	0.50	2.8	3.5	3.48	19.1
小計	37.1	小計		139.3	小計		18.6	小計		18.6	小計		120.8
計	105.10	合計		289.3	合計		60.1	合計		60.1	合計		229.3