

φ 200 m m 管 布 設 工 数 量 集 計 書

令和 7 年度 第 2 工区

計算書No.	区分	路 線 (掘削) 延 長	人孔等 による 減 長	掘削深	舗装構成		置 換 有 無	管 路 内 訳			平 均 掘削深	土 工								
					版厚	路盤 厚		管布設 埋戻し 延 長	直管内訳			掘 削 掘削幅		砂基礎		砂埋戻工		発生土 埋戻工	置換材 埋戻工	残 土 処分工
									片受 直管 本	プレ-ン ェント		W=	1.05m	t=	0.10m	埋戻厚	0.216			
		m	m	m	m	m	m	m	m	m	m	m	m3	m3	m3	m3	m3	m3		
1	補助	205.50	***	***	***	***	*	199.50	45	19.50	***	411.62	20.97	100.78	209.58		178.76			
	全体	205.50	***	***	***	***	*	199.50	45	19.50	***	411.62	20.97	100.78	209.58		178.76			
2	補助	205.50	***	***	***	***	*	200.40	47	12.40	***	547.14	21.03	101.23	343.02		166.00			
	全体	205.50	***	***	***	***	*	200.40	47	12.40	***	547.14	21.03	101.23	343.02		166.00			
3	補助	205.00	***	***	***	***	*	198.10	44	22.10	***	1:26	20.81	100.09	263.76		172.97			
	全体	205.00	***	***	***	***	*	198.10	44	22.10	***	466.06	20.81	100.09	263.76		172.97			
4	補助		***	***	***	***	*				***									
	全体		***	***	***	***	*				***									
5	補助		***	***	***	***	*				***									
	全体		***	***	***	***	*				***									
6	補助		***	***	***	***	*				***	※マンホール廻り水道配管用土工（17箇所分） 掘削2.0m3/1MH・埋め戻し1.4m3/1MH・残土処分0.7m3/1MH								
	全体		***	***	***	***	*				***	34.00			23.80		11.90			
総計	補助	616.00	***	***	***	***	*	598.00	136	54.00	***	1,458.82	62.81	302.10	840.16		529.63			
	全体	616.00	***	***	***	***	*	598.00	136	54.00	***	1,458.82	62.81	302.10	840.16		529.63			

マンホール番号		補単区分	路 線 (掘削) 延 長	人孔等 による 減 長	掘削深	舗装構成		置換有無	管 路 内 訳			土 工									
						版厚	路盤厚		管布設 埋戻し 延 長	直管内訳		平 均 掘削深	掘 削 掘削幅		砂基礎		砂埋戻工		発生土 埋戻工	置換材 埋戻工	残 土 処分工
										片受 直管 本	フ レ ー ン エ ン ト		W=	1. 05 m	t=	0. 10 m	埋戻厚	0. 516			
m		m	m	m	m	m	m	m	m	m	m3	m3	m3	m3	m3	m3	m3				
No. 116 - 1	補	18.50	0.60	2.63	0.04	0.29		17.90	4	1.90	2.24	42.74	1.88	9.04	24.32		15.72				
No. 116 - 2				1.84																	
No. 116 - 2	補	50.00	0.60	1.84	0.04	0.29		49.40	12	1.40	1.84	94.50	5.19	24.95	46.37		42.98				
No. 116 - 3				1.83																	
No. 116 - 3	補	10.00	0.60	1.85	0.04	0.29		9.40	2	1.40	1.88	19.32	0.99	4.75	9.22		9.08				
No. 116 - 4				1.90																	
No. 116 - 4	補	43.00	0.60	1.90	0.04	0.29		42.40	10	2.40	1.87	82.62	4.45	21.42	41.14		36.91				
No. 116 - 5				1.83																	
No. 116 - 5	補	26.00	0.60	1.91	0.04	0.29		25.40	6	1.40	1.87	49.96	2.67	12.83	24.64		22.58				
No. 116 - 6				1.82																	
No. 116 - 6	補	6.00	0.60	1.82	0.04	0.29		5.40	1	1.40	1.83	11.28	0.57	2.73	5.01		5.71				
No. 116 - 7				1.84																	
No. 116 - 7	補	18.00	0.60	2.04	0.04	0.29		17.40	4	1.40	2.07	38.37	1.83	8.79	20.54		15.55				
No. 116 - 8				2.09																	
No. 116 - 8	補	8.00	0.60	2.09	0.04	0.29		7.40	1	3.40	2.08	17.14	0.78	3.74	8.81		7.35				
No. 116 - 9				2.07																	
No. 116 - 9	補	10.00	0.60	2.09	0.04	0.29		9.40	2	1.40	2.08	21.42	0.99	4.75	11.19		8.99				
No. 116 - 10				2.06																	
No. 116 - 10	補	16.00	0.60	2.06	0.04	0.29		15.40	3	3.40	2.08	34.27	1.62	7.78	18.34		13.89				
No. 118 - 1				2.10																	
No.																					
No.																					
No.																					
No.																					
小 計	補助	205.50	***	***	***	***	*	199.50	45	19.50	***	411.62	20.97	100.78	209.58		178.76				
	全体	205.50	***	***	***	***	*	199.50	45	19.50	***	411.62	20.97	100.78	209.58		178.76				

計算書No.	2
--------	---

φ 200 m m 管 布 設 工 数 量 計 算 書

令和 7 年度 第 2 工区

マンホール番号		補単区分	路 線 (掘削) 延 長	人孔等 による 減 長	掘削深	舗装構成		置換有無	管 路 内 訳			土 工											
						版厚	路盤厚		管布設 埋戻し 延 長	直管内訳		平 均 掘削深	掘 削 掘削幅		砂基礎		砂埋戻工		発生土 埋戻工	置換材 埋戻工	残 土 処分工		
										片受 直管 本	フ レ ン エ ン ト		W=	1.05	m	t=	0.10	m				埋戻厚	0.516
			m	m	m	m	m		m		m	m3	m3	m3	m3	m3	m3	m3					
No. 118 - 1		補	49.00	0.90	2.33	0.04	0.29		48.10	12	0.10	2.23	112.68	5.05	24.30	64.85		40.62					
No. 118 - 2					2.12																		
No. 118 - 2		補	37.00	0.60	2.15	0.04	0.29		36.40	9	0.40	2.19	83.53	3.82	18.39	47.55		30.70					
No. 118 - 3					2.22																		
No. 118 - 3		補	11.00	0.60	2.22	0.04	0.29		10.40	2	2.40	2.08	23.56	1.09	5.25	12.38		9.80					
No. 118 - 4					1.94																		
No. 118 - 4		補	14.00	0.60	1.96	0.04	0.29		13.40	3	1.40	1.95	28.08	1.41	6.77	14.13		12.38					
No. 118 - 5					1.93																		
No. 118 - 5		補	25.00	0.60	1.93	0.04	0.29		24.40	6	0.40	1.95	50.14	2.56	12.33	25.72		21.56					
No. 118 - 6					1.96																		
No. 78 - 1		補	3.50	0.60	3.71	0.04	0.29		2.90		2.90	3.69	13.41	0.30	1.46	8.36		4.12					
No. 78 - 2					3.66																		
No. 78 - 2		補	55.00	0.60	3.66	0.04	0.29		54.40	13	2.40	3.53	201.55	5.71	27.48	147.60		37.55					
No. 120 - 1					3.40																		
No. 120 - 1		補	11.00	0.60	3.47	0.04	0.29		10.40	2	2.40	3.00	34.19	1.09	5.25	22.43		9.27					
No. 120 - 2					2.52																		
-																							
-																							
-																							
-																							
-																							
小 計	補助	205.50	***	***	***	***	*	200.40	47	12.40	***	547.14	21.03	101.23	343.02			166.00					
	全体	205.50	***	***	***	***	*	200.40	47	12.40	***	547.14	21.03	101.23	343.02			166.00					

計算書No.	3
--------	---

φ 200 m m 管 布 設 工 数 量 計 算 書

令和 7 年度 第 2 工区

マンホール番号		補単区分	路 線 (掘削) 延 長	人孔等 による 減 長	掘削深	舗装構成		置換有無	管 路 内 訳			土 工									
						版厚	路盤厚		管布設 埋戻し 延 長	直管内訳		平 均 掘削深	掘 削 掘削幅		砂基礎		砂埋戻工		発生土 埋戻工	置換材 埋戻工	残 土 処分工
										片受 直管 本	フ レ ン ェ ン ト		W=	1.05 m	t=	0.10 m	埋戻厚	0.516			
			m	m	m	m	m		m		m	m3	m3	m3	m3	m3	m3	m3			
No. 75 - 1		補	31.00	0.60	1.92	0.04	0.29		30.40	7	2.40	1.94	61.85	3.19	15.36	31.73		26.59			
No. 75 - 2					1.96																
No. 75 - 2		補	18.00	0.60	1.96	0.04	0.29		17.40	4	1.40	1.98	36.67	1.83	8.79	18.89		15.68			
No. 76 - 1					1.99																
No. 76 - 1		補	39.00	0.90	2.52	0.04	0.29		38.10	9	2.10	2.27	91.32	4.00	19.25	52.97		32.46			
No. 76 - 2					2.01																
No. 76 - 2		補	28.00	0.60	2.99	0.04	0.29		27.40	6	3.40	2.46	71.15	2.88	13.84	43.56		22.75			
No. 77 - 1 - 1					1.92																
No. 77 - 1 - 1		補	7.50	0.60	1.92	0.04	0.29		6.90	1	2.90	1.89	14.57	0.72	3.49	6.84		6.97			
No. 77 - 3 - 1					1.85																
No. 77 - 3 - 1		補	16.00	0.90	1.89	0.04	0.29		15.10	3	3.10	1.88	30.91	1.59	7.63	14.81		14.45			
No. 77 - 3 - 2					1.86																
No. 77 - 3 - 2		補	21.50	0.90	2.92	0.04	0.29		20.60	5	0.60	2.71	60.28	2.16	10.41	38.16		17.88			
No. 77 - 3 - 3					2.49																
No. 77 - 3 - 3		補	8.00	0.60	2.51	0.04	0.29		7.40	1	3.40	2.45	20.24	0.78	3.74	11.69		7.25			
No. 77 - 3 - 4					2.39																
No. 77 - 3 - 4		補	30.00	0.60	2.39	0.04	0.29		29.40	7	1.40	2.19	67.73	3.09	14.85	38.40		25.06			
No. 77 - 3 - 5					1.98																
No. 77 - 2 - 1		補	6.00	0.60	1.72	0.10			5.40	1	1.40	1.90	11.34	0.57	2.73	6.71		3.88			
No. 77 - 3 - 1					2.07																
小 計	補助	205.00	***	***		***	*	198.10	44	22.10	***	466.06	20.81	100.09	263.76		172.97				
	全体	205.00	***	***	***	***	*	198.10	44	22.10	***	466.06	20.81	100.09	263.76		172.97				

φ 200mm土 留 工 数 量 集 計 書

令和 7 年度 第 2 工区

計算書No.	区分	掘削 深	平均 掘削 深	掘削 幅	た て 込 み 簡 易 土 留								軽量鋼矢板工			
					H=1. 5m	H=2. 0m	H=2. 5m	H=3. 0m	H=3. 5m	H=4. 0m	H=4. 5m	H=5. 0m	H=3. 5m	H=4. 0m	支保工	
		m	m	m	m	m	m	m	m	m	m	m	m	m	2 段梁	3 段梁
1	補助	****	****	****		135. 00	70. 50									
	全体	****	****	****		135. 00	70. 50									
2	補助	****	****	****		39. 00	97. 00	11. 00		58. 50						
	全体	****	****	****		39. 00	97. 00	11. 00		58. 50						
3	補助	****	****	****		78. 50	105. 00	21. 50								
	全体	****	****	****		78. 50	105. 00	21. 50								
4	補助	****	****	****												
	全体	****	****	****												
5	補助	****	****	****												
	全体	****	****	****												
6	補助	****	****	****												
	全体	****	****	****												
総計	補助	****	****	****		252. 50	272. 50	32. 50		58. 50						
	全体	****	****	****		252. 50	272. 50	32. 50		58. 50						

計算書No.	2
--------	---

土留工数量計算書

令和 7 年度 第 2 工区

マンホール番号	補単区分	掘削深 m	平均掘削深 m	掘削幅 m	た て 込 み 簡 易 土 留								軽量鋼矢板工			
					H=1.5m	H=2.0m	H=2.5m	H=3.0m	H=3.5m	H=4.0m	H=4.5m	H=5.0m	H=3.5m	H=4.0m	支保工	
					m	m	m	m	m	m	m	m	m	m	2 段梁 m	3 段梁 m
No. 118 - 1	補	2.33	2.23	1.05			49.00									
No. 118 - 2		2.12														
No. 118 - 2	補	2.15	2.19	1.05			37.00									
No. 118 - 3		2.22														
No. 118 - 3	補	2.22	2.08	1.05			11.00									
No. 118 - 4		1.94														
No. 118 - 4	補	1.96	1.95	1.05		14.00										
No. 118 - 5		1.93														
No. 118 - 5	補	1.93	1.95	1.05		25.00										
No. 118 - 6		1.96														
No. 78 - 1	補	3.71	3.69	1.05						3.50						
No. 78 - 2		3.66														
No. 78 - 2	補	3.66	3.53	1.05						55.00						
No. 120 - 1		3.40														
No. 120 - 1	補	3.47	3.00	1.05				11.00								
No. 120 - 2		2.52														
小 計	補助	****	****	****		39.00	97.00	11.00		58.50						
	全体	****	****	****		39.00	97.00	11.00		58.50						

計算書No.	3
--------	---

土留工数量計算書

令和 7 年度 第 2 工区

マンホール番号	補単区分	掘削深 m	平均掘削深 m	掘削幅 m	た て 込 み 簡 易 土 留								軽量鋼矢板工			
					H=1.5m	H=2.0m	H=2.5m	H=3.0m	H=3.5m	H=4.0m	H=4.5m	H=5.0m	H=3.5m	H=4.0m	支保工	
					m	m	m	m	m	m	m	m	m	m	2 段梁 m	3 段梁 m
No. 75 1	補	1.92	1.94	1.05												
No. 75 2		1.96				31.00										
No. 75 - 2	補	1.96	1.98	1.05												
No. 76 - 1		1.99				18.00										
No. 76 - 1	補	2.52	2.27	1.05												
No. 76 - 2 -		2.01					39.00									
No. 76 - 2 -	補	2.99	2.46	1.05												
No. 77 - 1 - 1		1.92					28.00									
No. 77 - 1 - 1	補	1.92	1.89	1.05												
No. 77 - 3 - 1		1.85				7.50										
No. 77 - 3 - 1	補	1.89	1.88	1.05												
No. 77 - 3 - 2		1.86				16.00										
No. 77 - 3 - 2	補	2.92	2.71	1.05												
No. 77 - 3 - 3		2.49						21.50								
No. 77 - 3 - 3	補	2.51	2.45	1.05												
No. 77 - 3 - 4		2.39					8.00									
No. 77 - 3 - 4	補	2.39	2.19	1.05												
No. 77 - 3 - 5		1.98					30.00									
No. 77 - 2 - 1	補	1.72	1.90	1.05												
No. 77 - 3 - 1		2.07				6.00										
小 計	補助	****	****	****		78.50	105.00	21.50								
	全体	****	****	****		78.50	105.00	21.50								

計算書No.	1
--------	---

第 1 号 組立マンホール設置工数量計算書

令和 7 年度 第 2 工区

マンホール番号		補単区分	マンホール深	蓋＋受枠		底部工			副管		削孔数			可とう継手		コンクリート部材																		調整金具		ブロック据付工			転落防止用梯子				
				T14	T25	全	Co	砕	内	外	300	200	150	150	200	底版	躯体ブロック								直壁								斜壁		調整リング			25mmまで		45mmまで	3.0m以下	4.0m以下	4.0m超え
																	600	900	1200	1500	1800	2100	2400	300	600	900	1200	1500	1800	2100	2400	450	600	100	150	200	個						
		m	組	組	箇所	箇所	箇所	箇所	箇所	箇所	箇所	箇所	個	個	個	個	個	個	個	個	個	個	個	個	個	個	個	個	個	個	個	個	個	個	箇所	箇所	箇所	個					
No. 116 - 1		補				1						1		1																													
No. 116 - 3		補	1.74	1		1						1		2	1			1										1		1				1	1								
No. 116 - 5		補	1.80	1		1						1		2	1			1										1				1	1		1								
No. 116 - 7		補	1.93	1		1						1		2	1			1											1			1			1	1							
No. 116 - 9		補	1.98	1		1						1		2	1			1											1				1			1	1						
No. 118 - 1		補	2.22	1		1						1		2	1				1										1			1			1	1							
No. 118 - 2		補	2.05	1		1						1		2	1				1									1			1			1		1							
No. 118 - 4		補	1.86	1		1						1		2	1			1											1	1			1		1		1						
No. 118 - 6		単	3.48	1		1			1			1		2	1						1	1							1			1		1			1		1		1		
No. 78 - 1		補	3.60	1		1						1		2	1						1		1										1	1			1		1		1		
No. 120 - 1		補	3.36	1		1						2		3	1						1	1								1				1			1		1		1		
No. 75 - 1		補	1.81	1		1								1	1			1																1	1			1					
No. 76 - 1		補	2.41	1		1						1		2	1					1														1	1			1					
No. 76 - 2		補	2.88	1		1			1			1		2	1						1								1				1		1		1		1				
No. 77 - 3 - 1		補	1.99	1		1						2		3	1			1											1				1		1		1		1				
No. 77 - 3 - 2		補	2.81	1		1			1			1	1	1	2	1					1								1			1			1		1		1				
No. 77 - 3 - 3		補	2.40	1		1			1			1	1	1	2	1				1								1				1	1			1		1					
No. 77 - 3 - 5		単	3.37	1		1			2			1	1	1	2	1					1	1								1	1			1			1		1		1		
小 計	補助	****	15		15	1						17	2	2	32	15			7	2	2	2	2	1	1					4	7	3	4	8	10	5	13	2					
	全体	****	17		17	1		6				19	3	3	36	17			7	2	2	2	4	3	1					4	9	4	4	9	11	6	13	4		4			

令和 7 年度 第 2 工区

副管数量計算書

令和 7 第 2 工区

マンホール番号	補単区分	本管径 mm	副管高 m	副管設置工						副管材料							
				1.0m未満 箇所	1.0m以上 1.5m未満	1.5m以上 2.0m未満	2.0m以上 2.5m未満	2.5m以上 3.0m未満	3.0m以上 3.8m未満	十字管				直管		90度曲管	
					箇所	箇所	箇所	箇所	箇所	φ150 個	φ200 個	φ250 個	φ350 個	φ150 m	φ200 m	φ150 個	φ200 個
No. 118 - 6	単	200	1.63			1					1			1.30		1	
No. 76 - 2	単	200	0.97	1							1			0.64		1	
No. 77 - 3 - 2	単	200	1.05		1						1			0.72		1	
No. 77 - 3 - 3	単	200	1.38		1						1			1.05		1	
No. 77 - 3 - 5	単	200	1.50			1					1					1	
No. 77 - 3 - 5	単	200	1.86			1					1			1.53		1	
小計	補助		****														
	全体		****	1	2	3					6			5.24		6	

取付管布設・土工集計表

令和 7 年度 第 2 工区

工 種	項 目 ・ 規 格				単位	取 付 管		汚 水 枿		取 付 管 部 分		備 考
						VU φ 150		VU φ 200				
						全 体	補 助	全 体	補 助	全 体	補 助	
取付管布設工	取 付 管 路 布 設 延 長				m	35.60	34.20	24.80	23.40			
	布 設 材 料	ゴ ム 輪 受 口 片 受 直 管			m	35.60	34.20	24.80	23.40			
					本	9	9	7	6			4.0m/本
					自在曲管 φ 150	75°	個					
		0°	個	19		18						
		φ 150	60° 曲 管		個	14	14					
			90° 支管	150*150		個						
				200*150		個	14	14				
				250*150		個						
	300*150			個								
350*150		個										
汚水枿設置工	汚 水 枿			込が石	h≦1.0	個			2	2		
					1.0<h≦1.5	個			5	4		
					1.5<h≦2.0	個						
				T-8	h≦1.0	個			4	4		
					1.0<h≦1.5	個			6	6		
					1.5<h≦2.0	個			2	2		
				T-14	h≦1.0	個						
					1.0<h≦1.5	個						
					1.5<h≦2.0	個						
土 工	掘 削				m3					45.01	43.10	
	埋 戻	山 砂			m3					10.32	9.93	
		購入土（タンパ）			m3							
		良質発生土（タンパ）			m3					20.27	19.40	
	残 土				m3					22.47	21.53	

汚水取付管 土工数量計算書 本管 200 mm

令和 7 年度 第 2 工区

1 人孔No.	補 単 区 分	購入 土 埋 戻	本管部		取付部	宅 地 内			掘 削		掘 削 深		掘 削		舗 装		掘 削	山 砂	埋 戻 し			残 土
			土被り		占 用	所有者	柵深 H	柵 下	延 長 L (m)	本管部 H1 (m)	柵 部 H2 (m)	幅 W (m)	表 層 t (m)	路 盤 t (m)	(m3)	(m3)	(m3)	(m3)	H6 (m)	発生土 (m3)	購入土 (m3)	(m3)
			上/下 (m)	平均 (m)	CL～柵CL (m)		(m)	(m)														
116-8			1.77																			
116-9	補		1.75	1.76	3.00	田中 努	1.40	0.10	2.73	1.62	1.60	0.87	0.04	0.29	3.03	0.71	0.72	1.41				1.46
118-1			2.01																			
118-2	補		1.80	1.91	5.00	小倉 正春	1.40	0.10	4.73	1.64	1.60	0.87	0.04	0.29	5.28	1.36	0.73	2.50				2.50
118-2			1.84																			
118-3	補		1.91	1.88	2.00	小倉 正春	1.40	0.10	1.73	1.61	1.60	0.87	0.04	0.29	1.91	0.39	0.71	0.87				0.94
118-2			1.84																			
118-3	補		1.91	1.88	2.00	五位塚 美智子	1.40	0.10	1.73	1.61	1.60	0.87	0.04	0.29	1.91	0.39	0.71	0.87				0.94
118-2			1.84																			
118-3	補		1.91	1.88	2.00	久保田 はま子	1.50	0.10	1.73	1.71	1.70	0.89	0.04	0.29	2.06	0.39	0.81	1.01				0.94
118-5			1.62																			
118-6	補		1.65	1.64	2.00	飯野 勝夫	1.50	0.10	1.73	1.71	1.70	0.89	0.04	0.29	2.06	0.39	0.81	1.01				0.94
118-5			1.62																			
118-6	補		1.65	1.64	2.00	樋口 竹春	1.00	0.10	1.73	1.21	1.20	0.79	0.04	0.29	1.34	0.39	0.31	0.36				0.94
小 計	補 助														17.59	4.02	4.80	8.03				8.66
	全 体														17.59	4.02	4.80	8.03				8.66
合 計	補 助																					
	全 体																					

※宅地内の掘削深（H2）は標準図より柵深（H）に砂基礎厚0.1mを加えた

汚水取付管 土工数量計算書 本管 200 mm

令和 7 年度 第 2 工区

2	補 単 区 分	購入 土埋 戻	本管部		取付部	宅 地 内			掘 削 延 長 L (m)	掘 削 深		掘 削 幅 W (m)	舗 装		掘 削 (m3)	山 砂 (m3)	埋 戻 し			残 土 (m3)
			土被り		占 用 CL～柵CL (m)	所有者	柵深 H (m)	柵 下 (m)		本管部 H1 (m)	柵 部 H2 (m)		表 層 t (m)	路 盤 t (m)			H6 (m)	発生土 (m3)	購入土 (m3)	
			上/下 (m)	平均 (m)																
75-1			1.60																	
75-2	補		1.65	1.63	2.00	田中 努	0.90	0.10	1.73	1.11	1.10	0.77	0.04	0.29	1.21	0.39	0.21	0.24		0.94
76-2			2.67																	
77-1-1	補		1.60	2.14	2.00	清水 國広	2.10	0.10	1.73	2.31	2.30	1.01	0.04	0.29	3.04	0.39	1.41	1.90		0.93
76-2			2.67																	
77-1-1	補		1.60	2.14	2.00	永明院	1.40	0.10	1.73	1.61	1.60	0.87	0.04	0.29	1.91	0.39	0.71	0.87		0.94
76-2			2.67																	
77-1-1	補		1.60	2.14	2.00	河内 秀樹	0.80	0.10	1.73	1.01	1.00	0.75	0.04	0.29	1.08	0.39	0.11	0.12		0.95
77-2-1			1.40																	
77-2-1	補		1.40	1.40	2.00	相吉 くに子	1.20	0.10	1.73	1.41	1.40	0.83	0.04	0.29	1.62	0.39	0.51	0.61		0.94
77-3-2			2.60																	
77-3-2	補		2.60	2.60	4.00	相吉 文雄	2.50	0.10	3.73	2.73	2.70	1.09	0.04	0.29	8.14	1.04	1.82	5.65		1.86
77-3-2			2.60																	
77-3-3	補		2.17	2.39	2.00	堀内 文雄	1.20	0.10	1.73	1.41	1.40	0.83	0.04	0.29	1.62	0.39	0.51	0.61		0.94
77-3-3			2.17																	
77-3-3	補		2.17	2.17	2.00	河内 一秀	0.80	0.10	1.73	1.01	1.00	0.75	0.04	0.29	1.08	0.39	0.11	0.12		0.95
77-3-3			2.19																	
77-3-4	補		2.08	2.14	5.00	河内 秀樹	0.80	0.10	4.73	1.04	1.00	0.75	0.04	0.29	2.99	1.36	0.13	0.41		2.53
77-3-4			2.08																	
77-3-4	補		2.08	2.08	2.00	樋口 登	1.10	0.10	1.73	1.31	1.30	0.81	0.04	0.29	1.48	0.39	0.41	0.48		0.95
77-3-4			2.08																	
77-3-5	補		1.67	1.88	2.00	葦崎市青年家	1.00	0.10	1.73	1.21	1.20	0.79	0.04	0.29	1.34	0.39	0.31	0.36		0.94
77-3-5			1.67																	
77-3-5	単		1.67	1.67	2.00	樋口 登	1.40	0.10	1.73	1.61	1.60	0.87	0.04	0.29	1.91	0.39	0.71	0.87		0.94
小 計	補 助														25.51	5.91		11.37		12.87
	全 体														27.42	6.30		12.24		13.81
合 計	補 助														43.10	9.93		19.40		21.53
	全 体														45.01	10.32		20.27		22.47

※宅地内の掘削深 (H2) は標準図より柵深 (H) に砂基礎厚0.1mを加えた

令和 7 年度 第 2 工区

[illegible]

汚水取付管 管材数量計算書 本管 200 mm

令和 7 年度 第 2 工区

本管部				取 付 部	宅 地 内		L4 (m)	管 材											
人孔No.		土被り		占用 CL～桝CL (m)	所 有 者	桝深 H (m)		直 管		60° 曲管 (φ 150) (本)	90° 支管					0° 自在 曲管 (本)	蓋 (φ 200用)		
		上/下 (m)	平均 (m)					φ 200 (m)	φ 150 (m)		150*150 (本)	200*150 (本)	250*150 (本)	300*150 (本)	350*150 (本)		T-14 (個)	T-8 (個)	シカゲ石 (個)
75-1	補	1.60			田中 努	0.90	1.40	0.90	1.40	1		1				1			1
75-2		1.65	1.63	2.00															
76-2	補	2.67			清水 國広	2.10	1.40	2.10	1.40	1		1				1		1	
77-1-1		1.60	2.14	2.00															
76-2	補	2.67			永明院	1.40	1.40	1.40	1.40	1		1				1		1	
77-1-1		1.60	2.14	2.00															
76-2	補	2.67			河内 秀樹	0.80	1.40	0.80	1.40	1		1				1		1	
77-1-1		1.60	2.14	2.00															
77-2-1	補	1.40			相吉 くに子	1.20	1.40	1.20	1.40							1			1
77-2-1		1.40	1.40	2.00															
77-3-2	補	2.60			相吉 文雄	2.50	3.40	2.50	3.40							1		1	
77-3-2		2.60	2.60	4.00															
77-3-2	補	2.60			堀内 文雄	1.20	1.40	1.20	1.40	1		1				1		1	
77-3-3		2.17	2.39	2.00															
77-3-3	補	2.17			河内 一秀	0.80	1.40	0.80	1.40							1		1	
77-3-3		2.17	2.17	2.00															
77-3-3	補	2.19			河内 秀樹	0.80	4.40	0.80	4.40	1		1				1		1	
77-3-4		2.08	2.14	5.00															
77-3-4	補	2.08			樋口 登	1.10	1.40	1.10	1.40							1			1
77-3-4		2.08	2.08	2.00															
77-3-4	補	2.08			韮崎市青年家	1.00	1.40	1.00	1.40	1		1				1			1
77-3-5		1.67	1.88	2.00															
77-3-5	単	1.67			樋口 登	1.40	1.40	1.40	1.40							1			1
77-3-5		1.67	1.67	2.00															
小 計	補 助						20.40	13.80	20.40	7		7				11		7	4
	全 体						21.80	15.20	21.80	7		7				12		7	5
合 計	補 助						34.20	23.40	34.20	14		14				18		12	6
	全 体						35.60	24.80	35.60	14		14				19		12	7

舗装数量集計表（補助対象）

番 号	舗 装 版 切 断				舗 装 版 破 砕						廃 材 処 理		仮々復旧
	As		Co		As			Co			As	Co	As
	$t \leq 15$	$15 < t \leq 30$	$t \leq 15$	$15 < t \leq 30$	$t \leq 10$	$10 < t \leq 15$	$15 < t \leq 35$	$t \leq 10$	$10 < t \leq 15$	$15 < t \leq 35$	m ³	m ³	ton
	m	m	m	m	m ²	m ²	m ²	m ²	m ²	m ²			
1	822.00				1357.13						54.29		4.53
	402.40				812.15						32.49		
合 計	1224.40				2169.28						86.78		4.53

舗装復旧面積集計表（補助対象）

令和 7 年度 第 2 工区

舗 装 構 成								
工 種	路 床 置 換 (m ²)		下 層 路 盤 (m ²)					
材 料	置換材		RC40-0					
厚 さ	t= cm	t= cm	t= 20 cm	t= 18 cm	t= 45 cm	t= cm	t= cm	t= cm
数 量				630.52				

舗 装 構 成								
工 種	上 層 路 盤 (m ²)			表 層 (m ²)				
材 料	M40-0			As			Co	砂利
厚 さ	t= 8 cm	t= 11 cm	t= 10 cm	t= 4 cm	t= 5 cm	t= 3 cm	t= 12 cm	t= 10 cm
数 量		630.52		2,156.97				7.30

○ 不陸整正 = 2,156.97 − 630.52 = 1,526.45 m²

舗装面積計算表（補助対象）

No. 1

路線名	区分	現況舗装構成		復旧舗装構成		数量一覧			
		種別	厚(c m)	種別	厚(c m)				
116	路床改良					舗装版切断(m)	822.00	下層路盤(m ²)	423.86
118	下層路盤	RC40-0	18	RC40-0	18	舗装版破碎(m ²)	1,357.13	上層路盤(m ²)	423.86
78	上層路盤	M40-0	11	M40-0	11	廃材処理(m ³)	54.29	表層(m ²)	1,349.43
120	表層	As	4	As	4	路床改良(m ²)			
	仮々復旧					仮々復旧(t)			

測点	単距離	掘削幅	舗装幅	平均舗装幅	路盤面積	舗装面積	測点	単距離	掘削幅	舗装幅	平均舗装幅	路盤面積	舗装面積
116-1		1.05	2.50										
116-2	18.50	1.05	2.30	2.40	19.43	44.40							
116-3	50.00	1.05	2.50	2.40	52.50	120.00							
116-4	10.00	1.05	2.30	2.40	10.50	24.00							
116-5	43.00	1.05	2.20	2.25	45.15	96.75							
116-6	26.00	1.05	2.20	2.20	27.30	57.20							
116-7	6.00	1.05	2.30	2.25	6.30	13.50							
116-8	18.00	1.05	2.30	2.30	18.90	41.40							
116-9	8.00	1.05	2.40	2.35	8.40	18.80							
116-10	10.00	1.05	2.30	2.35	10.50	23.50							
118-1	16.00	1.05	3.30	2.80	16.80	44.80							
118-2	49.00	1.05	3.80	3.55	51.45	173.95							
118-3	37.00	1.05	4.00	3.90	38.85	144.30							
118-4	11.00	1.05	3.10	3.55	11.55	39.05							
118-5	14.00	1.05	3.40	3.25	14.70	45.50							
118-6	25.00	1.05	3.20	3.30	26.25	82.50							
							控除		1号	10.00		5.30	5.30
78-1		1.05	7.50						2号				
78-2	3.50	1.05	6.80	7.15	3.68	25.03			3号				
120-1	55.00	1.05	4.70	5.75	57.75	316.25			小型	8.00		2.40	2.40
120-2	11.00	1.05	3.70	4.20	11.55	46.20			0号				
							小計	411.00				431.56	1,357.13
							控除					7.70	7.70
							合計	411.00				423.86	1,349.43

舗装面積計算表（補助対象）

No. 2

路線名	区分	現況舗装構成		復旧舗装構成		数量一覧			
		種別	厚(c m)	種別	厚(c m)				
75	路床改良					舗装版切断(m)	402.40	下層路盤(m ²)	206.66
76	下層路盤	RC40-0	18	RC40-0	18	舗装版破碎(m ²)	812.15	上層路盤(m ²)	206.66
77-1	上層路盤	M40-0	11	M40-0	11	廃材処理(m ³)	32.49	表層(m ²)	807.54
77-3	表層	As	4	As	4	路床改良(m ²)			
	仮々復旧					仮々復旧(t)			

測点	単距離	掘削幅	舗装幅	平均舗装幅	路盤面積	舗装面積	測点	単距離	掘削幅	舗装幅	平均舗装幅	路盤面積	舗装面積
75-1			3.20										
75-2	31.00	1.05	3.40	3.30	32.55	102.30							
76-1	18.00	1.05	5.00	4.20	18.90	75.60							
76-2	39.00	1.05	3.70	4.35	40.95	169.65							
77-1-1	28.00	1.05	3.60	3.65	29.40	102.20							
77-3-1	7.50	1.05	3.80	3.70	7.88	27.75							
77-3-2	16.00	1.05	4.60	4.20	16.80	67.20							
77-3-3	21.50	1.05	3.90	4.25	22.58	91.38							
77-3-4	8.00	1.05	4.80	4.35	8.40	34.80							
77-3-5	30.00	1.05	4.20	4.50	31.50	135.00							
77-3-1		1.05	2.80										
77-3-1+2.2	2.20	1.05	2.90	2.85	2.31	6.27							
							控除		1号	7.00		3.71	3.71
									2号				
									3号				
									小型	3.00		0.90	0.90
									0号				
							小計	201.20				211.27	812.15
							控除					4.61	4.61
							合計	201.20				206.66	807.54

No. 3

路 線 名	区 分	現 況 舗 装 構 成		復 旧 舗 装 構 成		数 量 一 覧			
		種 別	厚 (c m)	種 別	厚 (c m)				
77-3	路床改良					舗装版切断 (m)	7.60	下層路盤 (m ²)	
	下層路盤					舗装版破碎 (m ²)	7.60	上層路盤 (m ²)	
	上層路盤					廢材処理 (m ³)	0.76	表層 (m ²)	7.30
	表層	砂利	10	砂利	10	路床改良 (m ²)			
	仮々復旧					仮々復旧 (t)			

[illegible]

No. 4

路 線 名	区 分	現 況 舗 装 構 成		復 旧 舗 装 構 成		数 量 一 覧			
		種 別	厚 (c m)	種 別	厚 (c m)				
78	路床改良					舗装版切断 (m)		下層路盤 (m ²)	
120	下層路盤					舗装版破碎 (m ²)		上層路盤 (m ²)	
	上層路盤					廢材処理 (m ³)		表層 (m ²)	
	表層					路床改良 (m ²)			
	仮々復旧			As	3	仮々復旧 (t)	4.53		

[illegible]