

φ 200 m m 管 布 設 工 数 量 集 計 書

令和 7 年 度 第 3 工 区

計算書No.	区分	路 線 (掘削) 延 長	人孔等 による 減 長	掘削深	舗装構成		置 換 有 無	管 路 内 訳			平 均 掘削深	土 工							
					版厚	路盤 厚		管布設 埋戻し 延 長	直管内訳			掘 削 掘削幅	砂基礎		砂埋戻工		発生土 埋戻工	置換材 埋戻工	残 土 処分工
									片受 直管 本	フ レ ン エ ン ト			基礎厚	管外径	埋戻厚				
		m	m	m	m	m	m	m	m	W=	1.05	m	t=	0.10	m	埋戻厚	0.516	m3	m3
1	補助	47.00	***	***	***	***	*	46.40	11	2.40	***	112.10	4.87	23.44	80.66			22.48	
	全体	71.50	***	***	***	***	*	70.00	15	10.00	***	156.75	7.35	35.36	108.42			36.28	
2	補助	302.20	***	***	***	***	*	295.00	69	19.00	***	663.34	30.98	149.02	367.03			255.52	
	全体	302.20	***	***	***	***	*	295.00	69	19.00	***	663.34	30.98	149.02	367.03			255.52	
3	補助		***	***	***	***	*				***								
	全体		***	***	***	***	*				***								
4	補助		***	***	***	***	*				***								
	全体		***	***	***	***	*				***								
5	補助		***	***	***	***	*				***								
	全体		***	***	***	***	*				***								
6	補助		***	***	***	***	*				***	※マンホール廻り水道配管用土工（8箇所分） 掘削2.0m3/1MH・埋め戻し1.4m3/1MH・残土処分0.7m3/1MH							
	全体		***	***	***	***	*				***	16.00			11.20			5.60	
総計	補助	349.20	***	***	***	***	*	341.40	80	21.40	***	775.44	35.85	172.46	447.69			278.00	
	全体	373.70	***	***	***	***	*	365.00	84	29.00	***	836.09	38.33	184.38	486.65			297.40	

マンホール番号		補単区分	路 線 (掘削) 延 長 m	人孔等 による 減 長 m	掘削深 m	舗装構成		置換有無	管 路 内 訳			土 工									
						版厚 m	路盤厚 m		管布設 埋戻し 延 長 m	直管内訳		平 均 掘削深 m	掘 削 掘削幅 W= 1.05 m		砂基礎 基礎厚 t= 0.10 m		砂埋戻工 管外径 0.216 埋戻厚 0.516		発生土 埋戻工 m3	置換材 埋戻工 m3	残 土 処分工 m3
										片受 直管 本	プレーン エント		m	m	m	m	m	m			
No. 89 - 1		補	37.00	0.15	2.12	0.10			36.85	9	0.85	2.38	88.58	3.87	18.62	64.38			17.05		
	2.64																				
No. 90 - 1		補	10.00	0.45	2.64	0.10			9.55	2	1.55	2.34	23.52	1.00	4.82	16.28			5.43		
	2.04																				
No. 96 - 2 - 1		単	8.00	0.30	1.51	0.10			7.70	1	3.70	1.58	12.43	0.81	3.89	6.99			4.66		
No. 96 - 2 - 2					1.64																
No. 96 - 2 - 2		単	16.50	0.60	1.64	0.10			15.90	3	3.90	1.96	32.22	1.67	8.03	20.77			9.14		
No. 96 - 3 - 1					2.28																

計算書No.	2
--------	---

φ 200 m m 管 布 設 工 数 量 計 算 書

令和 7 年度 第 3 工区

マンホール番号		補単区分	路 線 (掘削) 延 長	人孔等 による 減 長	掘削深	舗装構成		置換有無	管 路 内 訳			土 工									
						版厚	路盤厚		管布設 埋戻し 延 長	直管内訳		平 均 掘削深	掘 削		砂基礎		砂埋戻工		発生土 埋戻工	置換材 埋戻工	残 土 処分工
										片受 直管 本	ブレン ェント m		掘削幅	基礎厚	管外径 0.216	埋戻厚 0.516					
																	W=	1.05 m			
			m	m	m	m	m		m	本	m	m	m3	m3	m3	m3	m3	m3			
No. 88 - 1	補	37.50	0.90	2.86	0.04	0.29		36.60	9	0.60	2.42	93.71	3.84	18.49	56.65			30.77			
No. 90 - 1				1.97																	
No. 90 - 1	補	76.00	0.90	2.06	0.04	0.29		75.10	18	3.10	2.19	171.57	7.89	37.94	98.10			62.57			
No. 94 - 1				2.32																	
No. 94 - 1	補	28.50	0.90	2.34	0.04	0.29		27.60	6	3.60	2.15	63.14	2.90	13.94	34.89			24.37			
No. 96 - 1 - 1				1.96																	
No. 96 - 1 - 1	補	33.00	0.60	2.04	0.04	0.29		32.40	8	0.40	1.99	67.57	3.40	16.37	35.52			28.10			
No. 96 - 1 - 2				1.94																	
No. 96 - 1 - 2	補	25.00	0.60	1.94	0.04	0.29		24.40	6	0.40	1.93	49.61	2.56	12.33	25.21			21.60			
No. 96 - 1 - 3				1.92																	
No. 96 - 1 - 3	補	38.00	0.60	2.10	0.04	0.29		37.40	9	1.40	2.17	84.99	3.93	18.89	48.07			31.58			
No. 96 - 1 - 4				2.24																	
No. 96 - 1 - 4	補	19.00	0.60	2.24	0.04	0.29		18.40	4	2.40	2.10	41.10	1.93	9.29	22.30			16.32			
No. 96 - 1 - 5				1.96																	
No. 96 - 1 - 5	補	18.00	0.60	1.98	0.04	0.29		17.40	4	1.40	1.95	36.10	1.83	8.79	18.34			15.72			
No. 96 - 1 - 6				1.92																	
No. 96 - 1 - 6	補	20.00	0.60	1.92	0.04	0.29		19.40	4	3.40	1.94	39.90	2.04	9.80	20.25			17.40			
No. 96 - 3 - 1				1.95																	
No. 96 - 3 - 1	補	7.20	0.90	2.30	0.04	0.29		6.30	1	2.30	2.11	15.65	0.66	3.18	7.70			7.09			
No. 116 - 1				1.92																	
小 計	補助	302.20	***	***	***	***	*	295.00	69	19.00	***	663.34	30.98	149.02	367.03			255.52			
	全体	302.20	***	***	***	***	*	295.00	69	19.00	***	663.34	30.98	149.02	367.03			255.52			

φ200mm土留工数量集計書

令和 7 年度 第 3 工区

[illegible]

第1号組立マンホール設置工数量計算書

令和 7 年度 第 3 工区

[illegible]

令和 7 第 3 工区

[illegible]

取付管布設・土工集計表

令和 7 年度 第 3 工区

工 種	項 目 ・ 規 格				単位	取 付 管		汚 水 枥		取 付 管 部 分		備 考
						VU φ 150		VU φ 200				
						全 体	補 助	全 体	補 助	全 体	補 助	
取付管布設工	取 付 管 路 布 設 延 長				m	25.80	23.00	14.20	12.50			
	布 設 材 料	ゴ ム 輪 受 口 片 受 直 管			m	25.80	23.00	14.20	12.50			
					本	7	6	4	4			4.0m/本
		自在曲管 φ 150	75°	個								
			0°	個	12	10						
		φ 150	60° 曲 管		個	9	9					
			90° 支管	150*150	個							
				200*150	個	9	9					
				250*150	個							
	300*150			個								
		350*150	個									
汚水枥設置工	汚 水 枥			込が石	h≦1.0	個			2	2		
					1.0<h≦1.5	個			2	2		
					1.5<h≦2.0	個						
				T-8	h≦1.0	個			3	1		
					1.0<h≦1.5	個			5	5		
					1.5<h≦2.0	個						
				T-14	h≦1.0	個						
					1.0<h≦1.5	個						
					1.5<h≦2.0	個						
土 工	掘 削				m3					28.15	26.02	
	埋 戻	山 砂			m3					7.56	6.78	
		購入土（タンパ）			m3							
		良質発生土（タンパ）			m3					12.23	11.31	
	残 土				m3					14.56	13.45	

汚水取付管 土工数量計算書 本管 200 mm

令和 7 年度 第 3 工区

1 人孔No.	補 単 区 分	購入 土 埋 戻	本管部		取付部	宅 地 内			掘 削	掘 削 深		掘 削	舗 装		掘 削	山 砂	埋 戻 し			残 土
			土被り		占 用	所有者	柵深 H	柵 下	延 長	本管部 H1	柵 部 H2	幅 W	表 層 t	路 盤 t			埋 戻 し			
			上/下 (m)	平均 (m)	CL～柵CL (m)		(m)	(m)	L (m)								H6 (m)	発生土 (m3)	購入土 (m3)	
89-1			1.80																	
89-1	補		1.80	1.80	3.00	秋山 よし子	1.00	0.10	2.73	1.22	1.20	0.79	0.10		2.00	0.71	0.55	1.05		0.83
88-1			2.54																	
90-1	補		1.65	2.10	3.00	長田 忠雄	1.30	0.10	2.73	1.52	1.50	0.85	0.04	0.29	2.79	0.71	0.62	1.20		1.46
90-1			1.75																	
94-1	補		2.01	1.88	3.00	若尾 正巳	1.50	0.10	2.73	1.72	1.70	0.89	0.04	0.29	3.26	0.71	0.82	1.63		1.45
90-1			1.75																	
94-1	補		2.01	1.88	3.00	小野 基夫	1.50	0.10	2.73	1.72	1.70	0.89	0.04	0.29	3.26	0.71	0.82	1.63		1.45
94-1			2.03																	
96-1-1	補		1.65	1.84	3.00	秋山 勝治	1.20	0.10	2.73	1.42	1.40	0.83	0.04	0.29	2.57	0.71	0.52	0.99		1.47
96-1-2			1.63			山口コミュニ ティセンター														
96-1-3	補		1.60	1.62	2.00		1.00	0.10	1.73	1.21	1.20	0.79	0.04	0.29	1.34	0.39	0.31	0.36		0.94
96-1-2			1.63																	
96-1-3	補		1.60	1.62	3.00	消防詰所	0.80	0.10	2.73	1.02	1.00	0.75	0.04	0.29	1.71	0.71	0.12	0.22		1.47
96-1-2			1.63																	
96-1-3	補		1.60	1.62	3.00	小野 修一	1.40	0.10	2.73	1.62	1.60	0.87	0.04	0.29	3.03	0.71	0.72	1.41		1.46
小 計	補 助														19.96	5.36	4.48	8.49		10.53
	全 体														19.96	5.36	4.48	8.49		10.53
合 計	補 助																			
	全 体																			

※宅地内の掘削深（H2）は標準図より柵深（H）に砂基礎厚0.1mを加えた

汚水取付管 土工数量計算書 本管 200 mm

令和 7 年度 第 3 工区

2	補 単 区 分	購入 土 埋 戻	本管部		取付部	宅 地 内			掘 削	掘 削 深		掘 削	舗 装		掘 削	山 砂	埋 戻 し			残 土
			土被り		占 用	所有者	柵深 H	柵 下	延 長	本管部 H1	柵 部 H2	幅 W	表 層 t	路 盤 t						
			上/下 (m)	平均 (m)	CL～柵CL (m)		(m)	(m)	L (m)								H6 (m)	発生土 (m3)	購入土 (m3)	
96-1-3			1.79			根岸 清人	1.40	0.10	2.73	1.62	1.60	0.87	0.04	0.29	3.03	0.71	0.72	1.41		1.46
96-1-4	補		1.93	1.86	3.00															
96-1-4			1.93			小野 利廣	1.40	0.10	2.73	1.62	1.60	0.87	0.04	0.29	3.03	0.71	0.72	1.41		1.46
96-1-5	補		1.64	1.79	3.00															
96-2-1			1.20			功刀 達郎	0.80	0.10	1.73	1.01	1.00	0.75	0.10		1.00	0.39	0.34	0.40		0.56
96-2-1	単		1.20	1.20	2.00															
96-2-1			1.20			功刀 達郎	0.90	0.10	1.73	1.11	1.10	0.77	0.10		1.13	0.39	0.44	0.52		0.55
96-2-1	単		1.20	1.20	2.00															
小 計		補 助													6.06	1.42		2.82		2.92
		全 体													8.19	2.20		3.74		4.03
合 計		補 助													26.02	6.78		11.31		13.45
		全 体													28.15	7.56		12.23		14.56

※宅地内の掘削深（H2）は標準図より柵深（H）に砂基礎厚0.1mを加えた

本管 200 mm

令和 7 年度 第 3 工区

[illegible]

汚水取付管 管材数量計算書 本管 200 mm

令和 7 年度 第 3 工区

本管部			取 付 部	宅 地 内		L4 (m)	管 材												
人孔No.		土被り		占用 CL～桝CL (m)	所 有 者		桝深 H (m)	直 管		60° 曲管 (φ 150) (本)	90° 支管					0° 自在 曲管 (本)	蓋 (φ 200用)		
		上/下 (m)	平均 (m)					φ 200 (m)	φ 150 (m)		150*150 (本)	200*150 (本)	250*150 (本)	300*150 (本)	350*150 (本)		T-14 (個)	T-8 (個)	シカゲ石 (個)
96-1-3		1. 79																	
96-1-4	補	1. 93	1. 86	3. 00	根岸 清人	1. 40	2. 40	1. 40	2. 40	1		1				1		1	
96-1-4		1. 93																	
96-1-5	補	1. 64	1. 79	3. 00	小野 利廣	1. 40	2. 40	1. 40	2. 40	1		1				1		1	
96-2-1		1. 20																	
96-2-1	単	1. 20	1. 20	2. 00	功刀 達郎	0. 80	1. 40	0. 80	1. 40							1		1	
96-2-1		1. 20																	
96-2-1	単	1. 20	1. 20	2. 00	功刀 達郎	0. 90	1. 40	0. 90	1. 40							1		1	
小 計	補 助						4. 80	2. 80	4. 80	2		2				2		2	
	全 体						7. 60	4. 50	7. 60	2		2				4		4	
合 計	補 助						23. 00	12. 50	23. 00	9		9				10		6 4	
	全 体						25. 80	14. 20	25. 80	9		9				12		8 4	

鋪	裝	數	量	集	計	表
---	---	---	---	---	---	---

[illegible]

舗 装 復 旧 面 積 集 計 表

令和 7 年度 第 3 工区

舗 装 構 成								
工 種	路 床 置 換 (㎡)		下 層 路 盤 (㎡)					
材 料	置換材		RC40-0					
厚 さ	t= cm	t= cm	t= 20 cm	t= 18 cm	t= 45 cm	t= cm	t= cm	t= cm
数 量				312.50				

舗 装 構 成								
工 種	上 層 路 盤 (㎡)			表 層 (㎡)				
材 料	M40-0			As			Co	砂利
厚 さ	t= 8 cm	t= 11 cm	t= 10 cm	t= 4 cm	t= 5 cm	t= 3 cm	t= 12 cm	t= 10 cm
数 量		312.50		1,210.42				215.85

○ 不陸整正 = 1,210.42 − 312.50 = 897.92 ㎡

舗 装 面 積 計 算 表

No. 1

路 線 名	区 分	現 況 舗 装 構 成		復 旧 舗 装 構 成		数 量 一 覧			
		種 別	厚 (c m)	種 別	厚 (c m)				
88, 90	路床改良					舗装版切断 (m)	604.00	下層路盤 (m ²)	312.50
94, 96, 116	下層路盤	RC-40	18	RC40-0	18	舗装版破碎 (m ²)	1,215.03	上層路盤 (m ²)	312.50
	上層路盤	M40-0	11	M40-0	11	廢材処理 (m ³)	48.60	表層 (m ²)	1,210.42
	表層	As	4	As	4	路床改良 (m ²)			
	仮々復旧					仮々復旧 (t)			

測 点	単 距 離	掘 削 幅	舗 装 幅	平 均 舗 装 幅	路 盤 面 積	舗 装 面 積	測 点	単 距 離	掘 削 幅	舗 装 幅	平 均 舗 装 幅	路 盤 面 積	舗 装 面 積
88-1		1.05	2.80										
90-1	37.50	1.05	3.60	3.20	39.38	120.00							
94-1	76.00	1.05	3.90	3.75	79.80	285.00							
96-1-1	28.50	1.05	3.40	3.65	29.93	104.03							
96-1-2	33.00	1.05	3.20	3.30	34.65	108.90							
96-1-3	25.00	1.05	4.00	3.60	26.25	90.00							
96-1-4	38.00	1.05	3.50	3.75	39.90	142.50							
96-1-5	19.00	1.05	7.20	5.35	19.95	101.65							
96-1-5		1.05	7.20										
96-1-6	18.00	1.05	6.70	6.95	18.90	125.10							
96-3-1	20.00	1.05	4.60	5.65	21.00	113.00							
116-1	7.00	1.05	2.50	3.55	7.35	24.85							
							控 除		1号	7.00		3.71	3.71
									2号				
									3号				
									小型	3.00		0.90	0.90
									0号				
							小 計	302.00				317.11	1,215.03
							控 除					4.61	4.61
							合 計	302.00				312.50	1,210.42

舗装数量集計表（補助対象）

番 号	舗 装 版 切 断				舗 装 版 破 砕						廃 材 処 理		仮々復旧
	As		Co		As			Co			As	Co	As
	$t \leq 15$	$15 < t \leq 30$	$t \leq 15$	$15 < t \leq 30$	$t \leq 10$	$10 < t \leq 15$	$15 < t \leq 35$	$t \leq 10$	$10 < t \leq 15$	$15 < t \leq 35$	m ³	m ³	ton
	m	m	m	m	m ²	m ²	m ²	m ²	m ²	m ²			
1	604.00				1215.03						48.60		
合 計	604.00				1215.03						48.60		

舗装復旧面積集計表（補助対象）

令和 7 年度 第 3 工区

舗 装 構 成								
工 種	路 床 置 換 (m ²)		下 層 路 盤 (m ²)					
材 料	置換材		RC40-0					
厚 さ	t= cm	t= cm	t= 20 cm	t= 18 cm	t= 45 cm	t= cm	t= cm	t= cm
数 量				312.50				

舗 装 構 成								
工 種	上 層 路 盤 (m ²)			表 層 (m ²)				
材 料	M40-0			As			Co	砂利
厚 さ	t= 8 cm	t= 11 cm	t= 10 cm	t= 4 cm	t= 5 cm	t= 3 cm	t= 12 cm	t= 10 cm
数 量		312.50		1,210.42				134.70

○ 不陸整正 = 1,210.42 − 312.50 = 897.92 m²

舗装面積計算表（補助対象）

No. 1

路線名	区分	現況舗装構成		復旧舗装構成		数量一覧			
		種別	厚(c m)	種別	厚(c m)				
88, 90	路床改良					舗装版切断(m)	604.00	下層路盤(m ²)	312.50
94, 96, 116	下層路盤	RC-40	18	RC40-0	18	舗装版破碎(m ²)	1,215.03	上層路盤(m ²)	312.50
	上層路盤	M40-0	11	M40-0	11	廃材処理(m ³)	48.60	表層(m ²)	1,210.42
	表層	As	4	As	4	路床改良(m ²)			
	仮々復旧					仮々復旧(t)			

測点	単距離	掘削幅	舗装幅	平均舗装幅	路盤面積	舗装面積	測点	単距離	掘削幅	舗装幅	平均舗装幅	路盤面積	舗装面積
88-1		1.05	2.80										
90-1	37.50	1.05	3.60	3.20	39.38	120.00							
94-1	76.00	1.05	3.90	3.75	79.80	285.00							
96-1-1	28.50	1.05	3.40	3.65	29.93	104.03							
96-1-2	33.00	1.05	3.20	3.30	34.65	108.90							
96-1-3	25.00	1.05	4.00	3.60	26.25	90.00							
96-1-4	38.00	1.05	3.50	3.75	39.90	142.50							
96-1-5	19.00	1.05	7.20	5.35	19.95	101.65							
96-1-5		1.05	7.20										
96-1-6	18.00	1.05	6.70	6.95	18.90	125.10							
96-3-1	20.00	1.05	4.60	5.65	21.00	113.00							
116-1	7.00	1.05	2.50	3.55	7.35	24.85							
							控除		1号	7.00		3.71	3.71
									2号				
									3号				
									小型	3.00		0.90	0.90
									0号				
							小計	302.00				317.11	1,215.03
							控除					4.61	4.61
							合計	302.00				312.50	1,210.42

No. 2

路 線 名	区 分	現 況 舗 装 構 成		復 旧 舗 装 構 成		数 量 一 覧			
		種 別	厚 (c m)	種 別	厚 (c m)				
89	路床改良					舗装版切断 (m)	90.00	下層路盤 (m ²)	
	下層路盤					舗装版破碎 (m ²)	135.00	上層路盤 (m ²)	
90	上層路盤					廢材処理 (m ³)	13.50	表層 (m ²)	134.70
	表層	砂利	10	砂利	10	路床改良 (m ²)			
	仮々復旧					仮々復旧 (t)			

[illegible]